

AF-P900

PROCESS PUMP / Industrial Pumps

A high-flow pump reference for process water, utility transfer, and other continuous-duty services where the duty point, fluid compatibility, and maintenance access must be considered together.



PLATFORM ROLE	REFERENCE STATUS	DOCUMENT USE
Continuous-duty process transfer platform	Illustrative project concept	Early engineering conversation

TECHNICAL SPECIFICATION

PARAMETER	REFERENCE ENVELOPE
FLOW RATE	1,250 m3/h
MAXIMUM PRESSURE	40 bar
OPERATING TEMPERATURE	-20 C to 180 C
MATERIALS	316 SS / Duplex
DRIVE	Direct / VFD-ready

The values above are a reference envelope for concept discussions. Confirm duty, materials, performance, and compliance requirements against the approved project specification before procurement or manufacture.

AF-P900 / ENGINEERING NOTES

PROCESS PUMP / CONFIGURATION FRAMEWORK

The platform is configured around the operating envelope rather than selected from a single catalogue point. Use the prompts below to structure the application review.

DESIGN INTENT AND INTERFACES

ENGINEERING LENS	WHAT TO RESOLVE
Hydraulic intent	High-flow transfer with a defined continuous operating point and a documented minimum-flow strategy.
Process attention	Fluid properties, temperature, solids content, seal plan, suction conditions, and pipework losses.
Package boundary	Pump, driver, baseplate, isolation, instrumentation, and commissioning records are reviewed as one package.

CONFIGURATION REVIEW

ENGINEERING LENS	WHAT TO RESOLVE
Hydraulics	Confirm normal, minimum, and upset duty points against the project system curve before selecting an impeller or control strategy.
Materials	Use the stated material envelope as a starting point; verify chemistry, concentration, erosion, and corrosion allowance for the actual fluid.
Controls	A direct drive or VFD-ready arrangement can be evaluated against the operating profile and the required turndown.

ENGINEERING HANDOFF CHECKLIST

01	Duty point and fluid data recorded
02	Suction conditions and NPSH basis reviewed
03	Seal, bearing, and maintenance access confirmed
04	Utilities, instrumentation, and test basis agreed

REFERENCE NOTE	This document is a polished portfolio reference, not a certified data sheet. Exact performance, materials, interfaces, testing, and applicable requirements remain project-specific and require written confirmation.
----------------	---